

CENTRAL INSTITUTE OF MINING & FUEL RESEARCH. DHANBAD
(Council of Scientific & Industrial Research)

NOTICE INVITING TENDER
(Displaying in Notice Boards)

No. 23(334)/2008-GA/

Dated : 04/07/2008

Sealed tenders are hereby invited from bonafide govt. contractors, registered with CPWD, State, PWD, MES, Post and Telegraphs, Railway, Defence and other Govt. Department, CSIR or any of its laboratories, who have successfully completed at least 3 (three) similar type (equal to 40% of the estimated value) or 2 (two) similar type (equal to 50% of the estimated value) or 1 (one) similar type (equal to 80% of the estimated value) in last (5) five years.

Sl.	Description of work	Estimated Amount (Rs.)	Earnest money	Time of completion	Cost of Tender Documents
1.	Rectification of seepage at Qtr. no. V/4, IV/3, V/1, IV/3, II/17, SA-II/14, SA-I/24, III/22, SA-II/8, SA-II/36, SA-I/28, SA-III/1, II/64, II/54B, SA-I/26, I/23, I/30, SA-I/23, 45, III/10 at CIMFR, Barwa Road Campus.	83,612.00	1,700.00	15 Days	150=00

The following proof of documents in original or duly attested to be produced at the time of issuing tender paper and also to be submitted alongwith submission of tender for verification.

1. Xerox copy of PAN card.
2. Valid Jharkhand Sales Tax, Registration No. and Clearance certificates.
3. Completion certificate along with payment received of three similar works (including schedule) of values as mentioned above from an officer not below the rank of Executive Engineer of the concerned Department.

Tenders to be submitted in 2 Bid System

1. Part-I

(Technical Bid)

Consists of following documents

- a) Proof of documents as mentioned above (1-3)
- b) Earnest Money
- c) Cost of Tender documents (In case of tender document down loading from CIMFR Web site.)

2. Part-II

Consists of following documents

- a) Costing alongwith full specifications of the items involved in the work including all Taxes & Levies as per different laws.

Tender paper will be on sale from 08/07/2008 to 15/07/2008 on payment basis (Non refundable) on all working days of CIMFR up to 3:00 P.M. and will be also available in CIMFR website www.cmriindia.nic.in, that can be downloaded for submission. Those parties who submit their tenders after down loading, shall be required to pay the above mentioned amount (Cost of Tender Documents) in the form of Account Payee D.D. drawn in favour of Director, CIMFR, Dhanbad payable at SBI, Hirapur, alongwith their Technical Bid.

The Part-I & Part-II are to be individually sealed in separate envelopes and are to be put in a 3rd envelope which shall also be sealed and superscribed with the name of work in bold letters, address of the depositors and to be dropped in the Tender Box kept in the Office of the Administrative Officer, CIMFR, Dhanbad, after obtaining date, signature of Administrative Officer / Section Officer on or before 18/07/2008 at 3:00 P.M. and will be opened on the same day at 3:30 P.M., in presence of the intending tenderers or their authorized representatives whoever present themselves at the time of opening of tenders.

- Ø IT IS REQUIRED TO SUBMIT THE COST OF TENDER DOCUMENTS ALONG WITH TECHNICAL BID AS MENTIONED ABOVE.
- Ø EARNEST MONEY SHOULD BE DEPOSITED IN THE FORM OF ACCOUNT PAYEE DEMAND DRAFT PAYABLE AT SBI, HIRAPUR (CODE-1670) DHANBAD IN FAVOUR OF DIRECTOR, CENTRAL INSTITUTE OF MINING & FUEL RESEARCH, DHANBAD.
- Ø INCOMPLETE TENDERS, LATE / DELAYED TENDERS AS WELL AS TENDERS WITHOUT EARNEST MONEY SHALL BE SUMMARILY REJECTED.
- Ø DIRECTOR, CIMFR, RESERVES THE RIGHT OF ACCEPTING ANY TENDER IN PART OR FULL OR REJECTING ALL WITHOUT ASSIGNING ANY REASON.
- Ø LOWEST QUOTING FIRM HAS TO BE SUBMITTED PERFORMANCE GUARANTEE AS PER RULE BEFORE AWARDING THE JOB.

-Sd-
Head (Civil)

-Sd-
Administrative Officer

CENTRAL INSTITUTE OF MINING & FUEL RESEARCH. DHANBAD
(Council of Scientific & Industrial Research)

Name of work : Rectification of seepage at Qtr. no. V/4, IV/3, V/1, IV/3, II/17, SA-II/14, SA-I/24, III/22, SA-II/8, SA-II/36, SA-I/28, SA-III/1, II/64, II/54B, SA-I/26, I/23, I/30, SA-I/23, 45, III/10 at CIMFR, Barwa Road Campus.

<i>Sl.</i>	<i>Description of work</i>	<i>Qty.</i>	<i>Per</i>	<i>Rate</i>	<i>Amount</i>
1.	Providing and fixing of 100 mm dia. Sand cast Iron granting for gully trap.	12 nos.	Each		
2.	Providing and fixing of 75 mm dia. On wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 type A including jointing with seal ring conform to IS: 5382 leaving 10 mm gap for thermal expansion (i) single socket pipes. (Old pipes are to be deposited at Civil Maint. Sec.)	36.00	R.M.		
3.	Providing and fixing of P', S' or Q trap as per required C.I. trap of 4"x 3" etc. complete work after removing of old one including cutting of walls and finishing etc. complete.	14 nos.	Each		
4.	Providing and fixing of long pattern W.C. pan of size 580 mm Indian type including dismantling old one complete.	7 nos.	Each		
5.	Providing and fixing of 75 mm dia. C.I. S & S pipe as per IS:1729 with socket and applying and filling the joints with span yarn cement slurry and cement mortar 1:2 (1 cement: 2 fine sand) in S.C.I. / C.I. pipes, after removal of existing pipes if reqd. etc. complete.	21.00	R.M.		
6.	Providing and fixing a pair of white vitreous china foot rest of size 250x130x30 mm for W.C. pan including removal of old foot rest etc. complete.	7 Pairs	Each Pair		
7.	Providing and fixing M.S. holder bat clamps of 75 mm dia of approved design to sand cast iron / cast iron (span) pipe embedded in and including concrete blocks 10x10x10 cm of 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including cost of cutting holes and making good the walls.	30 nos.	Each		
8.	Providing and fixing single equal junction 75x75x75 mm C.I. of required degree with access door, insertion rubber washer 3 mm thick bolts and nuts complete work after removal of old existing one etc. complete.	4 nos.	Each		
9.	Repairs to plaster of thick 12 to 20 mm in patches of area 2.5 sqm and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 m. lead and old plaster etc. for cement mortar 1:4 (1 cement : 4 fine sand)	90.00	Sqm		

10.	40mm thick cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of noising steps etc. complete work after removal of old flooring.	125.00	Sqm		
11.	Providing and fixing of 150 mm dia C.P. brass shower rose with 15 or 20 mm inlet.	1 no.	Each		
12.	Providing and fixing PVC low level flushing cistern with manually controlled device (handle lever) conforming to IS:7231, with all fittings and fixtures, complete for 10 ltrs. Capacity – White (old cisterns are to be deposited to Civil Maintenance Section)	4 nos.	Each		
13.	Providing and fixing 15 mm dia nominal bore G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the wall internal work.	10.00	R.M.		
14.	Reinforcement cement concrete work in roofs etc. in C.C. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) etc. complete work.	0.11	Cum		
15.	Fixing of exhaust fan for making and cutting of brick in hole including fixing in block bolt in C.C. block 10x10x10 mm etc. complete work.	1 no.	Each		
16.	Centering and shuttering including strutting, propping etc. removal of form for roofs.	4.00	Sqm		
17.	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete	22.00	Kg.		
18.	40 mm thick marble chips flooring rubbed and polished to granolithic finish, under layer 34 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) and top layer 6 mm thick with white, black, chocolate, grey, yellow or green marble chips of size from 1mm to 4mm nominal size laid in cement marble powder mix 3:1 (3 cement : 1 mix powder) by weight in preparation of 4:7 (4 cement marble powder : 7 marble chips) by volume including cement slurry etc. complete including shade pigment with 50% white cement and 50% ordinary cement.	42.00	Sqm		
Total (Rs.)					